



Drawing:	Hardwood Floor/Ceiling Assembly
Project Name	
Contractor	
Notes:	<p>1) Subfloor should be clean and level- replace any damaged plywood sheets, acoustical caulk all gaps</p> <p>2) PHWU is installed with fabric facing up- loose laid- all seams and perimeter sealed with provided foil tape</p> <p>3) Install finished floor- follow manufacturers instructions and maintain a gap at the perimeter for expansion</p>